



OFFICE OF ENVIRONMENTAL REMEDIATION

100 Gold Street – 2nd Floor
New York, New York 10038

Daniel Walsh, Ph.D.

Director

Tel: (212) 788-8841

Fax: (212) 788-2941

REVISED DECISION DOCUMENT
NYC VCP and E-Designation Remedial Action Work Plan Approval

November 24, 2014

Re: Domino Sugar Site B – 270-290 Kent Avenue
Brooklyn Block 2414, p/o Lot 1
Hazardous Materials, Air Quality, and Noise “E” Designation
E Number E-337: Domino Sugar Project Action - CEQR 07DCP094K
OER Project Number 14EHAN584K / VCP Number 15CVCP003K

The New York City Office of Environmental Remediation (OER) has completed its review of the Remedial Action Work Plan (RAWP) dated August 13, 2014 with Stipulation Letter dated September 18, 2014 and the Remedial Action Plan (RAP) for Air Quality and Noise dated October 28, 2014 for the above-referenced project. These Plans were submitted to OER under the NYC Voluntary Cleanup Program and E-Designation Program.

The RAWP was released for public comment for 30 days as required by program rule. That comment period ended on September 15, 2014. There were no public comments.

Project Description

The future use of the Site will consist of residential, commercial, and community facility uses and will include a new 936,441 gross square foot (gsf) building rising to a maximum height of 390’6” and comprised of 35 above-grade floors. The building divides after the fifth floor into a northern and southern residential tower. The proposed development will include 754,508 gsf of residential floor area (680 residential units), 86,733 gsf of community facility floor area, 11,031 gsf of retail floor area, and 84,169 gsf of parking floor area (288 spaces).

The proposed building will include parking in the basement, first, and second floors, retail uses on the ground floor, community facility uses (comprised of a school) on floors 3 and 4, and residential uses on the ground floor (the residential lobby) and floors 5 through 35 (680 residential units). The building will have all market-rate residential units. The proposed development is one of three new buildings to be developed on Block 2414 Lot 1 as part of the approved Domino Sugar Project.

Statement of Purpose and Basis

This document presents the remedial action for the NYC Voluntary Cleanup Program and E-Designation project known as “Domino Sugar Site B” pursuant to Title 43 of the Rules of the City of New York Chapter 14, Subchapter 1 and the Zoning Resolution and §24-07 of the Rules of the City of New York.

Description of Selected Remedy for Hazmat

The remedial action selected for the Domino Sugar Site B site is protective of public health and the environment. The elements of the selected remedy are as follows:

1. Preparation of a Community Protection Statement and performance of all required NYCVCP Citizen Participation activities according to an approved Citizen Participation Plan;
2. Performance of a Community Air Monitoring Program for particulates and volatile organic carbon compounds;
3. Establishment of Site-Specific (Track 4) Soil Cleanup Objectives (SCOs);

4. Site mobilization involving Site security setup, equipment mobilization, utility mark outs and marking & staking excavation areas;
5. Performance of geophysical/test pits/trenches prior to start of building construction in proposed roads area and areas of the building footprint where excavation will not occur;
6. Completion of a Waste Characterization Study prior to excavation activities;
7. Excavation and removal of soil/fill exceeding Track 4 Site-Specific SCOs. For development purposes, 75% of the Site will be excavated, to depth of approximately 17 feet on the east end of Proposed Lot B, and approximately 5 to 7 feet towards the west end of Proposed Lot B. If soil/fill containing analytes at concentrations above Track 4 Site-Specific SCOs is still present at the base of the excavation after removal of all soil required for construction of the buildings is complete, additional excavation will be performed to meet Track 4 Site-Specific SCOs. In addition, four hotspot areas (Borings B-4, SB-4, SB-3, and BSB-5) identified during investigations will be excavated from 4 feet to 12 feet depths to achieve Track 4 SCOs. Approximately, 21,000 tons of soils will be excavated and removed from this Site;
8. Screening of excavated soil/fill during intrusive work for indications of contamination by visual means, odor, and monitoring with a PID. Appropriate segregation of excavated media on-Site;
9. Management of excavated materials including temporarily stockpiling and segregating to prevent commingling of contaminated material and non-contaminated materials;
10. Removal of nine (9) suspected underground storage tanks (USTs) along Kent Avenue sidewalk and other USTs (if encountered) and closure of petroleum spills (if evidence of a spill/leak is encountered during Site excavation) in compliance with applicable local, State and Federal laws and regulations;
11. Transportation and off-Site disposal of all soil/fill material at permitted facilities in accordance with applicable laws and regulations for handling, transport, and disposal, and this plan. Sampling and analysis of excavated media as required by disposal facilities. Appropriate segregation of excavated media on-Site;
12. Collection and analysis of end-point samples to determine the performance of the remedy with respect to attainment of SCOs;
13. Import of materials to be used for backfill and cover in compliance with this plan and in accordance with applicable laws and regulations;
14. Installation of a waterproofing membrane system below the cellar slab and slab on-grade portion of the building, as well as behind subgrade portions of foundation walls of the proposed building. The waterproofing membrane system will consist of Preprufe 300R and Bituthene 4000 as manufacturing by Grace. Preprufe 300 is a 1.2 mm (0.046in) thick HDPE film with a pressure sensitive adhesive that bonds to the poured concrete. Preprufe 300 will be installed below the building's cellar slab and on grade portion of the building slab along River Street. Bituthene 4000 is a flexible preformed waterproof membrane combining a high performance cross laminated, HDPE carrier film with a unique super sticky self-adhesive rubber bitumen compound. Bituthene 4000 will be installed behind the building's foundation walls to grade;
15. Construction and maintenance of an engineered composite cover consisting of the building's 2.5 ft and 5 ft thick pile-supported mat building slab to prevent human exposure to residual soil/fill remaining under the Site. Sidewalks and roadways will consist of a geotextile layer installed above a prepared subgrade, a 6 inch thick layer of a compacted aggregate base, and a 4 inch or 7 thick layer of concrete (sidewalks/driveways) or a layer of asphaltic concrete binder course below a asphaltic concrete top course (street);
16. Performance of all activities required for the remedial action, including permitting requirements and pretreatment requirements, in compliance with applicable laws and regulations;
17. Implementation of storm-water pollution prevention measures in compliance with applicable laws and regulations;
18. Submission of a Remedial Action Report (RAR) that describes the remedial activities, certifies that the remedial requirements have been achieved, defines the Site boundaries, describes all Engineering and Institutional Controls to be implemented at the Site, and lists any changes from this RAWP;
19. Submission of an approved Site Management Plan (SMP) in the RAR for long-term management of residual materials, including plans for operation, maintenance, inspection and certification of Engineering and Institutional Controls and reporting at a specified frequency; and
20. The property will continue to be registered with an E-Designation by the NYC Buildings Department. Establishment of Engineering Controls and Institutional Controls in this RAWP and a requirement that management of these controls must be in compliance with an approved SMP. Institutional Controls will include prohibition of the following: (1) vegetable gardening and farming; (2) use of groundwater without treatment rendering it safe for the intended use; (3) disturbance of residual contaminated material unless it is conducted in accordance with the SMP; and (4) higher level of land usage without OER approval.

Description of Selected Remedy for Air Quality

The elements of the remedial action selected for Air Quality for the Domino Sugar Site B site are as follows:

In order to satisfy the requirements of E-337, natural gas will be utilized at the site by four AERCO BMK 6.0 6000MBH and two AERCO BMK 3.0 3000MBH condensing boilers located on the roof. Both models are fitted with low NO_x burners whose emissions measure less than 30 ppm NO_x emissions at all firing rates when fired with natural gas. The boilers will provide domestic hot water for all residential units and heat for building areas including lobbies, common areas, retail areas, school space and corridors. A natural gas fired Tecogen InVerde Ultra 100 Ultra-Low Emissions Inverter-Based Cogeneration unit with waste heat recovery with a low-emission natural gas V-8 engine (NO_x emissions of < 0.07 lb/MWh, which corresponds to approximately 17 parts per million [ppm]) will be located in separate mechanical rooms on the roofs of each of Building B's two towers. Emergency power will be provided by a Kohler Power Systems natural gas generator (Model Number 200REZXB), which will be located at the roof level. All equipment specified complies with the low NO_x emission requirement of a concentration of less than 30 ppm NO_x at all firing rates. Stacks for the boiler chimney will be stainless steel AL-29-4C with a minimum height of three feet above the bulkhead, for a termination height of 413'6" above grade. For analysis purposes and to account for the site's irregular grading, elevation 0.0 National Geodetic Vertical Datum (NGVD) was considered "at grade" in both the air analysis and subsequent E Designation stack location requirement language as well as in the RAP.

Description of Selected Remedy for Noise

The elements of the remedial action selected for Noise for the Domino Sugar Site B site are as follows:

In order to satisfy the required window/wall attenuation, fixed and in-swing casement windows manufactured by F.A. & Partners, model FA100 will be utilized for all uses above the ground floor, including the school space. The glazing for these window will be 38.1 mm (1.5") IG (9.5 mm [3/8"] laminated exterior, 22.2 mm [7/8"] air space, 6.4 mm [1/4"] laminated interior). The proposed in-swing casement window with this glazing has been rated with an OITC of 35 as certified by the Lab Test Report included in the RAP. All windows (fixed, casement, and curtain wall) which will not have the same frame, gaskets, and glazing as the laboratory tested in-swing casement window will be tested per ASTM E-90 laboratory tests. The applicant commits to providing OER with an ASTM E-90 Lab Test Report for this/these window configuration(s) (glass and frame) prior to purchase and installation. The ground floor façades will use a storefront assembly manufactured by Kawneer, model Trifab VG (VersaGlaze) 451T Front, Store Front System, with a 1 1/8" glazing consisting of two sheets of glass separated by a 0.526" air space. The first sheet (exterior sheet) consists of two 0.128" thick pieces of glass with a 0.030" thick laminating sheet in between. The second sheet consists of two 0.130" thick pieces of glass with a .030" thick laminating sheet in between. The same storefront assembly would be used for all uses on the ground floor. The proposed ground floor storefront assembly has been rated with an OITC of 31.

Alternate Means of Ventilation for this project will be achieved by installing trickle vents in all residential apartment operable vents (Trimvent 90, SW and Patio Aluminum slot ventilator). AMV for the school and the commercial spaces will be provided via louvers (Greenheck EDJ-430) in the building's fascia to dedicated air handling equipment feeding the school and the commercial spaces. In accordance with the Mechanical Code of the City of New York, living areas shall be provided with a minimum of 15 cubic feet per minute (cfm) of outdoor air per person. Studio and one bedroom apartments will be equipped with trickle vents to provide a minimum of 30 cfm of outdoor air total; two bedroom apartments will be equipped with trickle vents to provide 45 cfm of outdoor air total. All bathrooms will be ventilated at a minimum rate of 20 cfm/bathroom. Trickle vents will be provided at a minimum frequency of one trickle vent per living room and/ or bedroom. Lobby, and common areas, and public corridors and commercial spaces will be provided with outside air in accordance with NYC Mechanical Code via louvers in the building's fascia or roof mounted intakes.

The remedies for Hazardous Materials, Air Quality, and Noise described above conform to the promulgated standards and criteria that are directly applicable, or that are relevant and appropriate and takes into consideration OER guidance, as appropriate.

11-24-2014



Date

Shana Holberton
Project Manager

11-24-2014



Date

Shaminder Chawla
Deputy Director

11-24-2014



Date

Maurizio Bertini
Assistant Director

cc: Marina Trejo, Two Trees Management Co. LLC - mtrejo@TwoTrees-Dumbo.com
Kevin Brussee, Environmental Business Consultants - kbrussee@ebcincny.com
Norabelle Greenberger, Philip Habib & Associates - ngreenberger@phaeng.com
Ismael Leyva - bsrivastava@ilarch.com
Daniel Walsh, Shaminder Chawla, Zach Schreiber, Hannah Moore
Shana Holberton, PMA-OER